



Project Name: Abbot Point Construction Camp Access Track

Client: Ports Corporation Queensland (PCQ)

Value: \$0.2M

Project Description:

This project involved the construction of an access track to the new construction camp for the Abbot Point Coal Terminal Expansion project. The access road crosses black soil farming land and is subject to frequent inundation during the wet season.

As part of the project, Allciv completed a re-design of the drainage and presented a cheaper, quicker alternative to reinforced box culverts which was accepted by the client.

Allciv also completed a redesign of the road pavement as the design was not suitable for the existing ground conditions.



Key elements of the works included:

- Very tight limits of clearing, being 5.5m from centerline of road.
- Construction of a 5 cell 750 diameter polypropylene ribbed pipe culvert and headwalls
- Importation of 2,000 cubic metres of decomposed granite general fill
- Road works, Drainage, two-coat seal and line marking.

Client Contact:

Mr Carrick Stokoe
General Manager Construction – Abbot Point
(07) 3224 7735

Allciv Contact:

Brett Thiele 0458 668 820
brett@allciv.com.au

